

MUNGER UNIVERSITY, MUNGER (BIHAR)

(ADMINISTRATIVE BLOCK, SHIASTRINAGAR, MUNGER, - 801201)

Tender no. KSS1/25

Date: 16/08/2025

1. Name of work **Construction of Entrance Gate in K.S.S. College, Lakhisarai**
(To be mentioned on The envelop)
1. Estimated cost 1941451/- (Nineteen lakhs forty one thousands four hundred and fifty two only) ..
2. Cost of B.O. Q. (non – refundable) ...Rs 2000/- (Two Thousand only)...
3. Amount of earnest money Rs. 38,830/- (Thirty eight thousand and thirty only).
4. Details of earnest money: In the shape of Six years N.S.C., five years post Office term deposit, Bank draft Bankers cheque etc. duly pledged in favour of the Registrar, Munger University.....
5. Time of completion: Six month...
6. Date and Time of sale of B.O.Q.(if purchased from Registrar office):...18/08/2025...
7. Date of Submission of sealed tender ...28/08/2025...+

Notes :-

- i. All casting shall compulsorily be done by using vibrator & mixer machine at pile work.
- ii. Unless otherwise specified, only TATA, SAIL, JSW and JINDAL T.M.T. Steel shall be used.
- iii. The agency shall have to keep at least three cubes at the site of the work for quality testing. The expenditure on quality test shall be borne by the Agency.
- iv. Only designation 100 A (First class) bricks shall be used.
- v. Only high class paints / Snowcem approved by E/I. and U.E. shall be Used.
- vi. Payments of works beyond agreement items if any shall be made as per S.R. plus.....% above or below on which the work is allotted to the agency.
- vii. It is compulsory to indicate total amount at the end after filling rate of each and every items separately failing which the tender is liable to be rejected.
- viii. No claims whatsoever shall be entertained in case of any delay in the payment.
- ix. Only potable water shall be used in the construction work for which arrangement is to be made by the agency itself.
- x. It is compulsory to execute agreement within (15) fifteen days from the date of allotment of work, failing which the allotment shall be cancelled and Earnest Money deposited at the time of submission of tender shall automatically be forfeited.
- xi. Foundation work shall be executed as per site condition.
- xii. 1% cess in addition to Sale-Tax, Income tax and royalty shall be deducted as per rules from contractor's bills.

K. S. S. College
16/08/25

Registrar/ Architect
(Dr. Ghanashyam Roy)
Registrar
Munger University, Munger-801201

MUNGER UNIVERSITY, MUNGER (BIHAR)

(ADMINISTRATIVE BLOCK, SHASTRINAGAR, MUNGER, - 801201)

B.O.Q

To be filled by the Contractor.

1. Name of work ... **Construction of Entrance Gate in K.S.S. College, Lakhisarai**
2. Date of tender.....
3. Quoted rate (both in words and figures)
 - (a) On SR' (w.e.f 01.01.2022)-.....(in words
 - (b) Below SR' (w.e.f 01.01.2022))-.....(in words
 - (c) Above SR' (w.e.f 01.01.2022))-.....(in words.....)
4. Registration No.
5. Details of I.T.C.C.
6. Details of GST
7. Details of labour license AS / GOVT LAWS
8. Time of complete required
By the contractor.
9. Time of complete Money deposited &
any other document if the tender wishes
to furnish.
10. Signature of Contractor
With full address & contact nos.

Krishna
16/08/25
Registrar/Architect
16/08/2025
(Dr. Ghanshyam Roy)
Registrar
Munger University, Munger-811201

MUNGER UNIVERSITY, MUNGER

NOTICE INVITING TENDER

Tender No. 01/25

Date 16/08/25

Sealed tenders are invited for "CONSTRUCTION OF ENTRANCE GATE IN K.S.S. COLLEGE, LAKHISARAI" in two bids (technical and financial bid in separate envelope) on approved Bill of Quantity from Registered Contractor of appropriate category in University works Dept./ Building construction dept. govt of Bihar, C.P.W.D. . to be eventually drawn in P.W.D. form no. F-2 will be received up to 1.00 P.M. on 29.-8.2025 by the Registrar, Munger University, Munger for the work and will be opened on the same day at 5.00 PM in the presence of tender or their authorized agents whoever may be present in the office of the Registrar. Munger University.

1. Tenderers should quote rates as below / above/ on B.O.Q. rates on the percentage basis both in figure and words of all items of works as a whole. They are also required to quote rate against each item of work separately.
2. The rate shall be inclusive of all taxes, royalties, carriages and all other incidental charges, payment of which will be sole responsibility of Contractors.
3. (a) The amount of estimate is 1941451/- (Nineteen lakhs forty one thousands four hundred and fifty one only))

(b) Percentage of rate quoted shall be up to two places after decimal and not lower and above .

$A-B/A \times 100 < \text{or} = 15\%$ will be deemed to be unworkable and tenders containing such rates will be out rightly rejected.

Where A = Estimated amount.

B = Quoted amount .

4. The work is to be completed within a period of six months from the date of issue of written order of commencement of the work.
5. All tenders are required to deposit Earnest Money of Rs Rs. 38,830/- (Thirty eight thousand and thirty only).in the shape of Six years N.S.C., five years post Office term deposit, Bank draft Bankers cheque etc. duly pledged in favour of the Registrar, Munger University .

Tender not accompanied with Earnest Money as specified above shall be out rightly rejected

5. All information can be obtained from the office of the Registrar, on submission of application addressed to the Registrar.
6. B.O.Q. can be obtained from the office of the Registrar, Munger University or download from university web site www.mungeruniversity.ac.in, Munger University, Munger on payment of Rs.2000/- (Two thousand only(Non – refundable)). If B.O.Q. is downloaded from website, cost of B.O.Q. should be attached alongwith tender papers, otherwise tender paper will be summarily rejected.
7. To obtain B.O.Q. from office, following papers must be produced to obtain B.O.Q. from Registrar office (i) upto date labour license, (ii) Sale Tax Registration & Clearance certificate,(iii) income Tax Clearance Certificate, (iv) Contractors Registration Certificate (v) Character Certificate on any working day during working hours except on the date of receiving tender.
8. The downloaded tender documents & B.O.Q. must be submitted to the authority along with (i) upto date labour license, (ii) Sale Tax Registration & Clearance certificate,(iii) income Tax Clearance Certificate, (iv) Contractors Registration Certificate (v) Character Certificate (vi) the cost of BOQ, (vii) earnest money.
9. Authority reserves the right to reject any or all the tenders received, no reason for the rejection of all or any of the tenders, whatever may be, will be given. Authority also reserves the right to distribute the work among two or more tenderers.
10. The Earnest Money of the successful tenderer will be forfeited in case he declines to sign the agreement of contract or to deposit balance of stipulated initial security money within ten days of being called upon to do so after acceptance of this tender.

[Signature]
16/08/2025
(Dr. Ghanshyam Roy)
Registrar
Munger University, Munger-811201

11. Conditional tender will not be accepted.
12. It will be obligatory on the part of the tenderer to keep his offer open for acceptance for the period of 180 days from the date of opening tenders.
13. special conditions will form the part of the agreement.
14. 'GST equal to 2% (two percent) shall be deducted from the bills.
15. Tenderer shall have to submit the Photostat copy of up to date income tax Clearance Certificate. Sales -Tax clearance Certificate, Labour License, Contractor's Registration Certificate, Character Certificate with tender papers, otherwise the tender shall be rejected.
16. 'Contractor should be registered with the Sales Tax dept. and a photocopy of the Registration Certificate should accompany with the tender paper otherwise the tender shall be rejected.
17. 'Bill of Quantity shall be issued to the contractors on production of Sales Tax Certificate, Contractors Registration Certificate, I.T. & S.T. Clearance Certificate & Character Certificate etc. in original.
18. 'A photocopy of the Character Certificate from the District Magistrate / Superintendent of Police duly signed by the competent authority should be attached with the tender paper otherwise the tender shall be rejected.


Krishna
16/08/25

ly Ray
16/08/2025
Registrar Architect
Munger University
(Dr. Ghanshyam Roy)
Registrar
Munger University, Munger-811201

MUNGER UNIVERSITY, MUNGER

SPECIAL CONDITIONS

1. (a) Tender must be accompanied by a letter stating works of similar nature and magnitude have been done by the tenderer with the name of work, value of contract, time allotted/actual time taken in completion of the work (stating briefly the reasons for delayed completion of work, if any) and a certificate from the Executive Engineer/ University Engineer /head of the institution under whom the work has been executed with the seal of his office.
 - (b) Details of other works of similar nature and magnitude completed by tenderer or in hand on the date of this tender with aforesaid details mentioned in the preceeding sub-para.
 - © Details of technical personnel's to be employed by the tenderer on this particular work starting their qualification and experience with supporting papers.
 - (d) Details with descriptive narration of plants and machineries for the period of at least six months to be used and its position regarding a viability of the same with the copies of certificates if any.
2. Tenderer must examine the site and the various aspects likely the construction/ renovation cost and then quote rate with full knowledge of all condition.
3. The work must be carried out strictly as per.
 - (a) Department specification and I.S.I specification.
 - (b) Design and Drawing duly approved by competent authority. Ignorance of specification and design and drawing shall not be any excuse and work found contrary to above shall not be acceptable and paid and shall be got removed at contractors cost.
5. All rate quoted in the tender should be for complete job including all carriage, royalty, GST, Income Tax and other taxes, the payment of which shall be sole Responsibility of the contractor .
2. Rules laid down in motor Vehicle Act –xx will have to be followed.
3. Labour Rules fixed from time to time shall have to be followed .
4. Stone chips, stone metals, bricks and sand confirm to I.S.I. specification and shall be as per samples approved by the Engineer in – Charge.
5. The centering and reinforcement for the R.C.C. work and wood work in doors and Windows and roof members should be got approved by Engineer- in- charge before taking up sequence of works.
6. Tender has to make complete arrangements for all accessories, plants and machines required for the execution of the work.
7. The contractor shall use tools and plants, machineries and equipments after duly approved by Engineer in – charge, for which hire charges will not be payable by the college/university.
8. Contractor shall have to maintain necessary technical organization for proper execution of works. He should employ only such persons who are skilled and experienced in their similar trades and working and the authorized University Engineer/architect shall be at liberty to object and require the contractor to remove any person employed by the contractor who is in his opinion is guilty of his conducts or is in compliant or negligent in proper performance of his duties and such person shall not be employed by the contractor without permission of the site incharge/Engineer.
9. No conditional tender will be accepted.
10. Structural steel should be cleaned of foreign materials before use, at the cost of contractors.



16/12/2025
(Dr. Ghanshyam Roy)
Registrar
Munger University, Munger-811201

11. No building materials shall be supplied by the University Works departments.
12. Any addition and alternation in the work must be done under of the competent authority. The contractor shall get such orders from competent authority in writing or duly entered in site order book taking sanction by officer not below the rank of Registrar/Assistant Engineer.
13. Site order book and reinforcement register shall be maintained by the junior Engineer on site which will be the property of the college/university. The contractor will mention the name of his authorized representative and attest his signature in the site order Book, who will receive instruction from college/university to comply them on his behalf(contractor).
In case the instructions are not being signed and complied by the authorized representative deliberately is deemed fit to cancel the work order under the relevant clauses of the agreement.
14. The value of work to be done should not exceed the agreement amount.
15. Payment will be made subject to availability of fund and no claim what so ever shall be entertained for non-payment on this score.
16. Quoted rates shall be based on leads from sources of essential/building materials as given in annexure-1.
17. Sand for brick masonry shall confirm to I.S.2160-1905 and fineness modules shall not be less than 1.8 fine silt passing 203 B.S. sieve or micron sieve shall not be more than 5% in any case.
18. Sand for concrete work shall be of approved grading and fineness modulus shall not be less than 2.2 in any case and for other works fineness modulus will be less than 1.8.
19. All necessary labour, land, materials, equipments etc for sampling and preparing test specimen for different type of construction with minimum desired frequency given below shall be provided by the contractor. Testing of materials and concrete may be arranged by the engineer in- charge in an approved laboratory at the cost of the contractor.
20. The contractor will have to submit a phased programmed for the completion of the major items of works after approval by the University Engineer shall be strictly adhered to. In addition he shall submit a phased fortnightly programmed of process of construction of each item so as to complete the work within the specified period of completion.
21. The authority reserves the right of deleting any item out of the tendered items without any violation of the contract.
22. Before executing agreement the tenders are required to produce a copy of registration and license for labour contract with labour dept. Govt. of Bihar as per labour contract Act. 1970 and its subsequent amendments, if any, without which the agreements may not be executed and Earnest Money may be forfeited if deemed fit.
23. All the materials to be used in works must be shown & got approved by the architect engaged by University before using them in works and brought to site for actual consumption in works.
24. Recovery on account of royalty & access on materials used in the bill be made from running on account bills to the event involved at rate approved by the concerned Govt. dept. From time to time during the entire period of contract till payment of final bill. Part or full amounts so deducted can only be refunded after obtaining clearance to the effect from the District Mining Officer.
25. All labourer are to be paid wages as per current, minimum wages Act .During the entire period of execution of work .
26. The contractor will provide labour butts, drinking water etc to the labours working at site and keep the site clean and tidy at his own cost as per rules and regulations of the Govt . of Bihar and central Govt. of which be should keep himself fully conversant and upto date .
27. All materials to be supplied by the contractor for use in work should get approved by the engineer/archtect in – charge prior to their use in works. All rejected materials shall have to be removed promptly atest within 10 day after rejection from the site otherwise the in – charge can dispose them off in any way he likes and for which no claim what so ever will be payable. The cost involved in their removal will also be recovered from the contractor and a certificate to this effect from the Engineer – in –charge shall be final bindings and conclusive on the contractor

16/8/2018
Dr. Ghanshyam Roy
Registrar
Munger University, Munger-811201

28. No. claim will be entertained for other items of work if done by the contractor unless order in writing by competent authority is available, verbal orders will not be binding on either side .
29. Payment may be completely denied for particular unfinished items of work , if deemed fit by the authority.
30. The contractor will not be compensated for any loss due to increase in hire or running either by central state or semi – Govt.Private bodies.
31. The contractor shall be responsible for all sorts of accidents occurred due to mismanagement of the contractor who shall be responsible to pay any damage or compensation on account of such accident.
32. The department will not pay compensation for the loss incurred due to :
- (i) Labour strikes
 - (ii) Payments to labours arising out of the award by labour tribunal for any part of the strike period or enhanced wages.
 - (iii) Any losses suffered due to war or enemy action whether declared or undeclared.
 - (iv) Fire, Famine, epidemics, riots or any other natural calamities.
 - (V) Stoppage of work due to any cause of circumstances.
33. GST shall be charged 1% /GST /CGST from the Bills.
34. Contractor should be registered with the sales tax dept. and a photo of the registration certificate should accompany with the tender paper.
35. A photo copy of character certificate obtained from the District Magistrate / Superintendent of Police duly signed by them should be attached with the tender paper otherwise the tender shall be rejected.

Kishore
16/08/25


16/08/2025
Registrar/Architect
Munger University
(Dr. G. Anshyam Roy)
Registrar
Munger University, Munger-811201

MUNGER UNIVERSITY, MUNGER
(Administrative Block, Shastrinagar, Munger – 811201)

B.O. Q

Papers /Copies of Documents to be attached with tenders :

1. Upto date labour licence No.....
2. I.T.Clearance.....
3. Sales Tax No / Vat No.....
4. Character certificate:
5. Registration in appropriate categories:
6. Payment certificate / credential certificate:
.....
.....
7. Time of completion:
8. Details of Earnest Money deposited :
.....
.....
9. Any other document if the
Tenders may like to submit:

University Engineer/architect

MUNGER UNIVERSITY
(Administrative Block, Shastrinagar, Munger – 811201)

DECLARATION
(To be filled in the contractor / agency)

I sri -----son of Sri-----of

Village / mohalla-----P.O-----

P.S-----Distt-----Telephone/mobile no-----

Hereby declare that under any circumstances I would not sublet the work of construction of

.....if

allotted to me . I further declare that I would undertake the execution of agreement and all official works my self. The execution of works, preparation of bills and receipt of bills etc. shall be done directly by me and not by any of my authorized persons . if at any stage it is found that the work has been sublet or is being sublet the tender / allotment of work will be cancelled and the EMD/ESD. shall be forfeited.

Signature

Place : -----

Mo:-----

Date : -----


Note : The tender is liable to be rejected if not accompanied with this declaration form duly filled in .

KARYANAND SHARMA SMARK COLLEGE, LAKHISARAI
MUNGER UNINVERSITY, MUNGER
WORK :-BILL OF QUANTITY FOR CONSTRUCTION OF ENTRANCE GATE AT KSS COLLEGE, LAKHISARAI, BIHAR BASED ON CURRENT SOR OF 2022


Rates are based on SOR 2022 (w.e.f. 01.01.2022) for Civil & SOR 2023 (w.e.f. 01.09.2023) for Electrical Works

BUILT UP AREA=


S. No	Item Code ref. to BCD sor 2022	Description of Items	Qty	Unit	Rate (ref. As per Bcd SOR 2022)	Amount (In Rs.)
		EARTHWORK AND FOINDATION				
1	20.2.1	Boring, Providing and installing cast in situ single under reamed piles of specified diameter and length below pile cap in M-25 cement concrete, to carry a safe working load not less than specified, excluding the cost of steel reinforcement but including the cost of boring with bentonite solution and the length of the pile to be embedded in pile cap etc. all complete. (Length of pile for payment shall be measured upto to the bottom of pile cap) :	32.00	METER	902.60	
		4MTRX8=32 M				
		conc vol.-3.14x0.3x0.3x32/4=2.26				
2	20.4.1	Extra over item No. 23.3 for providing additional bulb in under reamed piles, under specified dia meter (Only the quantity of extra bulbs are to be paid).				
		4x2x1=8,	8.00	each	1621.60	
		conc vol.-3.14x0.6x0.9x0.9x0.25x4x8=12.20/4=3.5				
3		Earth work in excavation in foundation trenches or drains(not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All Kinds of soil.				
		FOOTING	#REF!			
		TIE BEAM	#REF!			
	2.8.1		16.57	cum	360.70	
4	2.26	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead	2.96	cum	123.90	
6		Supplying and Filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing, including carriage of material complete.				
	2.28		9.17	cum	281.40	



	0.00	SUB HEAD TOTAL				
		CEMENT CONCRETE				
6		Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering-all work upto plinth level.				
		1:2:4 (1 Cement 2 coarse sand 4 graded stone aggregate 20mm nominal size)				
	4.5.1		3.88	cum	5341.10	
7	4.12	Extra for providing and mixing water proofing material in cement concrete work in the proportion	22.00	per 50 kg cement	57.18	
	0.00	SUB HEAD TOTAL				
		REINFORCED CEMENT CONCRETE				
8		Centring and shuttering including strutting, propping etc. and removal of form for				
a		Foundations, footings, bases of columns etc. for mass concrete.				
	5.9.1		5.95	sqm	211.60	
b		suspended floor, roofs, slab				
	5.9.3		4.68	sqm	437.50	
c		Lintel Beam, Plinth Beam, along direction				
	5.9.5		12.65	sqm	404.70	
d		Columns C1 under plinth				
	5.9.6		22.42	sqm	494.40	
f		edge of slab and breaks in floor and wall				
	5.9.16.1		2.48	sqm	133.20	
g		Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete				
		conc. Vol.-1597.42 m ³ steel required=39.99x141.12kg/m ³ =5643.00 kg				
a)	5.22.7A	Thermo-Mechanically Treated bars TMTC-500-8mm dia	643.00	Kg	94.50	
b)	5.22.7B	Thermo-Mechanically Treated bars TMTC-500-10mm	1800.00	Kg	92.60	
c)	5.22.7C	Thermo-Mechanically Treated bars TMTC-500-12mm dia & above	1500.00	Kg	90.80	
d)	5.22.7D	Thermo-Mechanically Treated bars TMTC-500-16mm dia & above	1000.00	Kg	91.70	
e	5.22.7E	Thermo-Mechanically Treated bars TMTC-500-20mm dia & above	500.00	Kg	91.70	
	5.22.1	Mild steel 6.00 mm dia	200.00	KG	95.70	
10		Providing and laying in position machine batched, machine mixed and machine vibrated design mix				
a)		All work upto plinth level				
	5.33A.1		2.19	cum	4718.90	
b)		Column				
	5.33A.2.1		11.21	cum	5293.50	
c)		All work from plinth level upto floor V level - Beams, planth beams, girders, bressumers, cantilevers, Suspended floors lintels roofs and staircases including spiral staircases, shelves etc				
	5.2.2		4.73	cum	5670.00	



11	5.330.4	Add or deduct for providing richer or leaner mixes respectively at all floor levels (a) Providing M-35 grade R.C.C. instead of M-20 grade R.C.C.	16.89	cum	38.18	
	0.00	SUB HEAD TOTAL				
		BRICK WORK				
12		Brick work with bricks of class designation 100A in foundations and plinth in Cement mortar 1:4				
	6.112/1	net vol. of brick work (A)-(B)	7.42	cum	5017.90	
13	6.3A	Extra for Brick work in superstructure above plinth level upto floor V cum	7.42	cum	842.20	
14		Providing designation 100 A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I				
	11.72		29.89	SQM	283.30	
15	8.13.1	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent	128.00	SQM	3605.20	
16	app	providing and fixing stainless steel lettering work of size 0.30 mtr. With all complete job	56.00	each	1150.00	
	app	size 0.15 mtr.	40.00	each	650.00	
		STEEL WORK				
17		Providing and fixing M.S. grills of requirement pattern in frames of windows etc. with M.S. flats, square or round bars etc all complete				
		MAIN GATE	#REF!			
		side gate	#REF!			
			#REF!			
	9.48.2	wt of steel @ 43.04kg = 25.55x43.04=1099.672	1099.76	kg	135.10	
		FINISHING				
	13.26	neat cement punning	4.46	sqm	40.50	
18		15 mm cement plaster on rough side of single or half brick wall of mix 1:4 (1 cement: 4 coarse sand)				
		TOP	45.24			
	13.12.2		126.11	sqm	176.40	
19	13.38.4	Extra for providing and mixing water proofing material in proportion recommended by the manufacturers	126.11	sqm	8.20	



20	13 80A 2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer over the plastered wall surface to prepare the surface even and smooth complete.	126.11	sqm	105.40	
21	13 46 1	finishing walls with acrylic smooth exterior paint of required shade including priming coat of exterior primer	126.11	sqm	137.00	
22	13 118	Forming groove of uniform size from 12x12 mm and upto 25x15 mm in plastered surface as per approved pattern using wooden battens, nailed to the under layer including removal of wooden battens, repairs to the edges of plaster panel and finishing the groove complete as per specifications and direction of the Engineer-in-Charge	125.00	METER	47.10	
23	13 81 1	applying primer coat with ready mixed pink or grey primer of approved and manufacture on STEEL work all complete as per direction of E/I	30.16	sqm	39.70	
24	13 82.1	Applying priming coat With ready mixed zinc chromate yellow primer of approved brand and manufacture on steel galvanized iron/steel works	30.16	sqm	83.50	
	0.00	SUB HEAD TOTAL				
		DISMANTLING & DEMOLISHING				
25	15 7 4	Demolishing of Brick work including stacking of servicable material and disposal of unservicable material within 50 m lead in cement mortar	48.00	cum	823.70	
26	15 2.1	Demolishing cement concrete including disposal of material within 50m lead 1:3:6 or richer mix	14.50	cum	970.90	
27	15 3	Demolishing of R.C.C. work including stacking of steel bars and disposal of unservicable material within 50m lead	11.28	cum	1411.20	
28	15 5	Extra for cutting reinforcement bars in R.C.C. or R.B. work (Payment shall be made on the cross sectional area of R.C.C or R.B. work)	21.00	per RCC	489.50	
29	15 3	Removing mortar from bricks and cleaning bricks including stacking within a lead of 50m (stacks of cleaned bricks shall be measured): From brick work in cement mortar	46.00	cum	2706.20	
30		carriage of materials				
a		Local sand, (5 KM)	9.2	sqm	310.47	
b		coarse sand, (5KM)	48.68	cum	1218.36	
c		Stone chips (18KM)	55.2	cum	3454.51	
d		Bricks (8KM)	5055.00	P/0	840.43	
e		cement (5KM)	22.61	Mt	518.08	
f		steel (5KM)	5.64	Mt	518.08	
		sub head				
31		SEIGNIORAGE FEES				
A		Coarse Sand	48.68	cum	17.58	
B		Local Sand	9.2	cum	14.19	
C		Stone Chips	55.2	cum	59.54	
		sub head				
		total amount			say	
		ADD 6% GST BEYOND 12%, MULTIPLYING FACTOR -0.0536				
				AMOUNT		

